



Decommissioning your waste disposal system

Please remove the pigs from the property and decommission the waste disposal system per the following instructions:

- (a) Stop waste water drainage flow to the tank;
- (b) Allow water inside cesspool/septic tank to recede;
- (c) Excavate 1~2 feet around the entire tank to a depth of 2 feet down;
- (d) Excavate 5 feet from the tank wall along the inflow and out flow pipes;
- (e) Remove both 5 foot sections of pipe and dispose of them at the Futiga landfill;
- (f) Demolish the top of the tank and allow the pieces to fall into the tank;
- (g) Demolish the tank walls to a point 1 foot below the surface of the surrounding ground and dispose of the concrete into the tank;
- (h) Fill in the tank and the excavated area with CLEAN fill soil;
- (i) **DO NOT USE THE WASTE AS FERTILIZER!** Untreated (non-composted) sewage used as fertilizer poses a health threat to those exposed to it and may contaminate groundwater and nearby streams.

In addition to, and for further explanation of these procedures, please view the standard AS-EPA schematic of the Piggery Septic Tank Demolition Procedures, Sheet A-1.